

# DIAMOND CONSTRUCTION

35 Beaverson Blvd., Suite 12C, Brick, New Jersey 08723  
Phone: (732) 262-7449 Fax: (732) 262-7795  
mdai@diamond-const.com

---

Date: April 25, 2018  
Attention: Michael Coolidge – Director of Buildings and Grounds  
Address: 67 Windeler Rd  
Howell, NJ 07731  
Phone: 732-751-2499, Ext. 4080  
Fax: 732-901-0543  
Email: mcoolidge@howell.k12.nj.us  
Subject: Asphalt Work at Southard Community Center  
115 Kent Rd, Howell, NJ 07731

---

## Proposal 4

### **1. BASE PRICE: Asphalt Pavement Repair at Southard Community Center.**

- Equipment, labor, and material costs for the complete pavement reconstruction of the existing asphalt surface delineated as being in need of repair at the Southard Community Center. Cost includes saw-cutting a square perimeter around the area to be repaired, all preparatory work consisting of excavation not to exceed 4", sub-base repairs to broken/missing asphalt where necessary, sweeping/cleaning of any loose rocks/dirt, the application of bituminous asphalt base course as required, bituminous asphalt tac-coat, bituminous asphalt surface course, and material disposal.
- Installation of 2" bituminous asphalt base course and 2" of bituminous asphalt surface course.
- **Approximate size of proposed work area is: 15' x 15' = 225 SF**
- Asphalt debris to be disposed of by Diamond Construction.
- Sub-base shall be 4" dense graded aggregate material.
- Application of tac-oil around perimeter of repair to be included.
- Includes any clean-up and site restoration in the proposed work area.

**Total Cost of BASE PRICE, Item 1:**

**\$ 5,400.00**

### **2. ALTERNATE PRICE: Asphalt Milling and Paving at Southard Community Center**

- Equipment, labor, and material costs for the asphalt milling and asphalt resurfacing of the right-side parking lot at Southard Community Center. Includes the surface milling of 2" off the existing asphalt parking lot, asphalt prep work consisting of sweeping/cleaning of loose rocks/dirt, construction keyways at adjoining pavements, asphalt tack coat, and the placement/compaction of new hot mix asphalt for the new asphalt resurfacing.
- Mill existing asphalt to a depth not to exceed 2"
- New asphalt will be 2" FABC asphalt surface course
- Includes 1000 SF of asphalt base repair (as needed)
- **Approximate size of the total proposed work area is: 12,000 SF**
- Project duration: 3 – 4 days.
- Includes all clean-up and site restoration in the proposed work area.
- Striping to include stalls, handicapped symbols, and fire/no parking lanes.

**Total Cost of ALTERNATE PRICE, Item 2:**

**\$ 44,000.00**

- ***Pavement repair and concrete/brick repair to be performed pursuant to ED-DATA contract #6887 package 24A (Macadam Paving) and Contract #6888 package 24B (Masonry and Concrete). Pricing is in accordance with services performed appurtenant to the aforementioned trades listed above.***

We are pleased to submit this proposal for work. Please circle the accepted scope of work, please sign below and return to Diamond Construction. This proposal is valid for 30 days. If you have any questions, please call us at 732-262-7449. Thank you.

  
Name and Signature of Authorizing Person

  
Date Accepted